

GRAND AVENUE PEDESTRIAN BRIDGE RELOCATION – BID SCHEDULE

ITEM NO.	CDOT NO.	CONTRACT ITEM	NOTES	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
1	201-00000	CLEARING AND GRUBBING		L S	1		
2	203-00060	EMBANKMENT MATERIAL (COMPLETE IN PLACE)		CY	5,500		
3	203-00100	MUCK EXCAVATION		CY	10		
4	206-00000	STRUCTURE EXCAVATION		CY	545		
5	206-00100	STRUCTURE BACKFILL (CLASS 1)		CY	33		
6	206-00200	STRUCTURE BACKFILL (CLASS 2)		CY	358		
7	206-01500	COFFERDAM	SEE PROJECT SPECIAL PROVISION	L S	1		
8	207-00210	STOCKPILE TOPSOIL		CY	530		
9	208-01000	EROSION CONTROL	SEE PROJECT SPECIAL PROVISION	L S	1		
10	210-00030	RESET WATER SERVICE	YARD HYDRANTS	EACH	2		
11	210-00510	REBUILD PORTIONS OF PRESENT STRUCTURE	BRIDGE REPAIR	L S	1		
12	212-00006	SEEDING (NATIVE)		ACRE	0.4		
13	213-00150	BONDED FIBER MATRIX		ACRE	0.7		
14	216-00201	SOIL RETENTION BLANKET (STRAW-COCONUT) (BIODEGRADABLE CLASS 1)		SY	1,750		
15	216-00301	TURF REINFORCEMENT MAT (CLASS 1)		SY	50		
16	304-06000	AGGREGATE BASE COURSE (CLASS 6)		TON	514		
17	503-01000	MICROPILE	(UNIT TYPE CHANGED BY ADDENDUM 1)	L.S.	1		
18	506-00000	RIPRAP		CY	80		
19	512-00118	BEARING DEVICE (SLIDE)		EACH	8		
20	512-00119	BEARING DEVICE (PINNED)		EACH	4		
21	514-00200	PEDESTRIAN RAILING (STEEL)	PORTIONS OF NEW RAILING ON BRIDGE	LF	305		

GRAND AVENUE PEDESTRIAN BRIDGE RELOCATION – BID SCHEDULE

ITEM NO.	CDOT NO.	CONTRACT ITEM	NOTES	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
22	514-01020	PEDESTRIAN RAILING (TIMBER)	ALONG PATH	LF	490		
23	519-03000	THIN BONDED EPOXY OVERLAY	ENTIRE DECK SURFACE	SY	508		
24	601-03040	CONCRETE CLASS D (BRIDGE)		CY	167		
25	601-25760	PRECAST CONCRETE DECK PANEL (6 INCH)	RIVER SPAN	SF	2,100		
26	601-40000	MASONRY VENEER		SF	73		
27	602-00000	REINFORCING STEEL	NON-COATED (BLACK) REBAR	LB	22,200		
28	603-30013	12 INCH PLASTIC END SECTION		EACH	2		
29	603-50004	4 INCH PLASTIC PIPE		LF	60		
30	603-50006	6 INCH PLASTIC PIPE		LF	16		
31	603-50012	12 INCH PLASTIC PIPE		LF	56		
32	604-19000	INLET SPECIAL		EACH	1		
33	608-00025	CONCRETE BIKEWAY (5 INCH)		SY	1320		
34	609-21900	CURB AND GUTTER TYPE 2 (SPECIAL - BAJA RED)		LF	285		
35	620-00020	SANITARY FACILITY		EACH	2		
36	626-00000	MOBILIZATION		L S	1		
37	630-10000	TRAFFIC CONTROL		L S	1		
38	630-80359	PORTABLE MESSAGE SIGN PANEL		DAY	20		
39	700-70010	F/A MINOR CONTRACT REVISIONS		F A	1	\$ 20,000.00	

(A) TOTAL BASE BID \$ _____

(TOTAL BASE BID – WORDS)

BID ALTERNATE 1 – ASPHALT TRAIL ALTERNATE

Total of Bid Alternate 1 to be added to Base Bid minus Item 33 (Concrete Bikeway – 5 Inch)

ITEM NO.	CDOT NO.	CONTRACT ITEM	NOTES	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
40	304-06000	AGGREGATE BASE COURSE (CLASS 6)	ADDITIONAL BASE COURSE FOR ASPHALT SECTION	TON	159		
41	403-33721	HOT MIX ASPHALT (GRADING SX) (75) (PG 58-28)	ASPHALT TRAIL ALTERNATE	TON	208		
42	403-33721	ASPHALT REINFORCEMENT GEOGRID	ASPHALT TRAIL ALTERNATE	TON	560		

(B) TOTAL BID ALT. 1 \$ _____

(TOTAL BID ALTERNATE 1 – WORDS)

BASE BID (A) \$ _____

ITEM 33 (CONCRETE BIKEWAY – 5 INCH) (C) \$ _____

(D) SUBTOTAL (A) - (C) \$ _____

BID ALTERNATE 1 (B) \$ _____

TOTAL (D) + (B) \$ _____

BID ALTERNATE 2 – CONNECTOR TRAIL AND STAIRS

Total of Bid Alternate 2 to be added to Base Bid

ITEM NO.	CDOT NO.	CONTRACT ITEM	NOTES	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
43	201-00000	CLEARING AND GRUBBING	ADDITIONAL CLEAR & GRUB FOR CONNECTOR	L S	1		
44	304-06000	AGGREGATE BASE COURSE (CLASS 6)	ADDITIONAL BASE COURSE FOR CONNECTOR	TON	12		
45	608-00025	CONCRETE BIKEWAY (5 INCH)	ADDITIONAL CONCRETE FOR CONNECTOR	SY	46		
46	601-03000	CONCRETE CLASS D	SLOPE PAVING AND STAIR FOOTINGS	CY	26		
47	602-00000	REINFORCING STEEL	REBAR FOR SLOPE PAVING AND STAIR FOOTINGS	LB	1,100		
48	621-00650	PEDESTRIAN STAIR STRUCTURE	INCLUDES HAND RAILING	EA	3		

(E) TOTAL BID ALT. 2 \$ _____

(TOTAL BID ALTERNATE 2 – WORDS)

BASE BID (A)	\$	_____
BID ALTERNATE 2 (E)	\$	_____
TOTAL (A) + (E)	\$	_____

BID ALTERNATE 3 – IRRIGATION AND LANDSCAPING

Total of Bid Alternate 3 to be added to Base Bid

ITEM NO.	CDOT NO.	CONTRACT ITEM	NOTES	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
49	623	MOBILIZATION		L S	1		
50	623	IRRIGATION SYSTEM	INSTALLED, COMPLETE AND IN PLACE	L.S.	1		
51	214	WHITE FIR	INSTALLED, COMPLETE AND IN PLACE	EA	6		
52	214	COLORADO BLUE SPRUCE	INSTALLED, COMPLETE AND IN PLACE	EA	6		
53	214	SPRING SNOW CRABAPPLE	INSTALLED, COMPLETE AND IN PLACE	EA	12		
54	214	GRO-LOW SUMAC	INSTALLED, COMPLETE AND IN PLACE	EA	4		
55	214	CHOKECHERRY	INSTALLED, COMPLETE AND IN PLACE	EA	38		
56	214	GAMBLE OAK	INSTALLED, COMPLETE AND IN PLACE	EA	31		
57	214	NEARLY WILD ROSE	INSTALLED, COMPLETE AND IN PLACE	EA	6		
58	214	SASKATOON SERVICEBERRY	INSTALLED, COMPLETE AND IN PLACE	EA	25		
59	214	McKAYS WHITE POTENTILLA	INSTALLED, COMPLETE AND IN PLACE	EA	6		
60	214	ROCKY MOUNTAIN JUNIPER	INSTALLED, COMPLETE AND IN PLACE	EA	5		
61	214	CHINESE LILAC	INSTALLED, COMPLETE AND IN PLACE	EA	9		

(F) TOTAL BID ALT. 3 \$ _____

(TOTAL BID ALTERNATE 3 – WORDS)

BASE BID (A)	\$	_____
BID ALTERNATE 3 (F)	\$	_____
TOTAL (A) + (F)	\$	_____

SUBMITTED BY:

Firm Name* _____
Address _____
City _____ **State** _____ **Zip** _____

* Insert "Corporation, Partnership", etc.

Name _____
Signature _____
Title _____
Phone _____

Address the envelope as follows:

**City of Glenwood Springs
City Clerk's Office
101 West 8th Street
Glenwood Springs, CO 81601**