

City of Glenwood Springs  
Procurement Department  
101 West 8<sup>th</sup> Street  
Glenwood Springs, Colorado 81601



**ADDENDUM NUMBER FOUR FOR  
7<sup>th</sup> STREET SANITARY SEWER AND  
STREETSCAPE BEAUTIFICATION PROJECT  
BID NUMBER BD 2018-054**

**THIS ADDENDUM MUST BE ACKNOWLEDGED.**

**THIS ADDENDUM SHALL BECOME A PART OF THIS SOLICITATION.**

**The following information is being added or amended as indicated as a part of the Invitation to Bid:**

The Bid Schedules for the 7<sup>th</sup> Street Streetscape Beautification – Phase 1 and Phase 2 have been revised with regard to the stone pavers. The City shall supply the stone pavers for Phase 1, but the **Contractor shall supply the stone pavers for Phase 2.** Additional line items have been added to the Bid Schedules. Stone paver materials are to be ordered from Coldspring USA to match the pavers supplied by the City for Phase 1.. Contact [Lisa Hennen](mailto:Lisa.Hennen@cityofglenwood.com) @ 800.328.5040 or Eric Scarborough @ 303.887.0911 for material pricing and order information.

**This addendum must be acknowledged.**

**This Addendum may be faxed to 970/945-2597, submitted to [bidresponse@cogs.us](mailto:bidresponse@cogs.us) (include BD2018-054 in the subject line), or be included with your bid submittal.**

PRINT OR TYPE YOUR INFORMATION

Name of Company: \_\_\_\_\_ Fax: \_\_\_\_\_  
Address: \_\_\_\_\_ City/State: \_\_\_\_\_ Zip: \_\_\_\_\_  
Contact Person: \_\_\_\_\_ Title: \_\_\_\_\_ Phone: \_\_\_\_\_  
Authorized Representative's Signature: \_\_\_\_\_ Phone: \_\_\_\_\_  
Printed Name: \_\_\_\_\_ Title: \_\_\_\_\_ Date: \_\_\_\_\_

**BD2018-054  
November 29, 2018**

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
1 A	1	LS	Mobilization, Demobilization and Incidentals: including but not limited to: all permits, coordination, labor, equipment, all other materials, services, safety, utility locates, excavations, soil preparations, site grading, vertical adjustments to existing utility structures or other items not individual itemized but required to effect construction, initiation, and completion of the project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
2 A	1	LS	Performance and Payment Bonds.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
3 A	1	LS	Construction Surveying and As-built Mapping: including but not limited to: all materials, labor and equipment necessary for establishing property line control, providing construction stakes, resetting damaged property corners or control markers, asbuilt mapping of all installed and encountered underground piping, for a complete project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
4 A	1	LS	Traffic Control: including but not limited: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
5 A	1	LS	Testing of Materials and Quality Assurance: including but not limited: coordination, material sampling, field and lab testing, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
6 A	1	EA	Removal of Fire Hydrant: including but not limited to: excavation, removal, hauling, delivery of salvaged materials, disposal, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
7 A	1	LS	Removal and Salvage of Materials (Signs, Posts, Bases, Lights, Furniture, Frames & Grates, etc.): including but not limited to: excavation, removal, hauling, delivery of salvaged materials, disposal of waste, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
8 A	1,740	SF	Removal of Concrete Sidewalk, Flatwork, Curb and Pavers: including but not limited to: removal, hauling, disposal, sawcuts, salvage of pavers and dome plates, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
9 A	8,090	SF	Removal of Asphalt (Disposal): including but not limited to: removal, stockpiling, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
10 A	4,110	SF	Removal of Asphalt (Planing/Milling): including but not limited to: removal, stockpiling, hauling, disposal, planing/milling, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
11 A	250	LF	Pressure Grout of Retired Sewer Pipe: including but not limited to: formwork, plugging, furnishing, hauling, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
12 A	1	LS	Erosion and Sediment Control: including but not limited to: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
13 A	430	LF	Trenching, Bedding & Backfill for Electric and Irrigation Conduits and Boxes: including but not limited to: coordination with City Electric Dept. (City to supply conduit, wire, pull boxes), excavation, bedding, conduit/wire/pull box installation, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
14 A	525	LF	Electric and Irrigation Conduits (2"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
15 A	7	EA	Electric or Irrigation Box (Concrete): including but not limited to: coordination with City Electric Dept., excavation, bedding, box, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
16 A	3	EA	Electrical Outlet Receptacle: including but not limited to: coordination with City Electric Dept., furnishing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
17 A	1	LS	Electrical System Wire and Electrician: including but not limited to: materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
18 A	2	EA	Light Pole Base: including but not limited to: coordination with City Electric Dept., excavation, bedding, backfill, compaction, concrete base (pole/lamp/wiring provided by others), all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
19 A	70	LF	Irrigation Main Extension(s): including but not limited to: excavation, bedding, backfill, compaction, conduit sleeving, pipe, valves, fittings, connections, boxes, testing, encasements, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
20 A	1	LS	Irrigation Sprinkler System (to 3 Trees): including but not limited to: excavation, bedding, backfill, compaction, conduit sleeving, tubing, valves, fittings, heads, connections, boxes, control wire, testing, encasements, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
21 A	1	LS	Irrigation Control System: including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
22 A	1	EA	1"Ø Water Service: including but not limited to: excavation, bedding, backfill, compaction, connection, pipe, fittings, plugs, joint restraints, curb stop, valve box, Nyloplast cover, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
23 A	1	EA	2"Ø Water Service: including but not limited to: excavation, bedding, backfill, compaction, connection, pipe, fittings, plugs, joint restraints, curb stop, valve box, Nyloplast cover, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
24 A	1	EA	Fire Hydrant Assembly (Hydrant and Riser Supplied by City): including but not limited to: excavation, bedding, backfill, compaction, joint restraints, fittings, conductivity wire, polywrap, thrust blocks, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
25 A	1	LS	Mobilization for Temporary Bypass Pumping: including all labor and materials, complete and in place for a completed project (QUANTITY STATED BY BIDDER).		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
26 A	7	Day	Temporary Bypass Pumping (Peak Flow 200-250 gpm): including all labor and materials, complete and in place for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
27 A	2	EA	Sanitary Sewer Manhole: including but not limited to: furnishing, hauling, casting, formwork, reinforcement, consolidation, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
28 A	148	LF	10" Sanitary Sewer Main: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
29 A	200	LF	10" Sanitary Sewer Main with Concrete Joint Encasement: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, concrete, forms, bond breaker, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
30 A	1	EA	New Sanitary Sewer Service (Sta: 3+08.80): including but not limited to: furnishing, hauling, excavation, bedding, backfill, compaction, connection, pipe, fittings, cleanouts, covers, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
31 A	1	EA	New Sanitary Sewer Service (Future Restroom): including but not limited to: furnishing, hauling, excavation, bedding, backfill, compaction, connection, pipe, fittings, cleanouts, covers, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
32 A	1	EA	New Sanitary Sewer Service (near Colorado Ave.): including but not limited to: furnishing, hauling, excavation, bedding, backfill, compaction, connection, pipe, fittings, cleanouts, covers, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
33 A	3	EA	Reconnect Sanitary Sewer Service: including but not limited to: furnishing, hauling, excavation, bedding, backfill, compaction, connection, pipe, fittings, cleanouts, covers, conductivity wire, appurtenances, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
34 A	238	LF	Curb and Gutter (IB, IIB, IM, IIM or Special): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)



**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
35 A	800	SF	4" Standard Gray Concrete (Sidewalks) over 6" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
36 A	196	SF	6" Standard Gray Concrete (Ramp, Driveway, Band) over 6" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
37 A	115	SF	8" Colored Concrete Pavement over 8" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
38 A	12	SF	Detectable Warning Plate (at Crosswalk): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

<b>Item No.</b>	<b>Estimated Quantity</b>	<b>Unit</b>	<b>Description and Unit Price in Words</b>	<b>Unit Price</b>	<b>Total Price</b>
39 A	1,182	SF	Paver Installation (Sand Set): including but not limited to: coordination with City Public Works Dept. (City to supply concrete/clay pavers/spacers), aggregate base course, geogrid, filter fabric, sand setting bed, compaction, concrete base slab, furnishing, hauling, formwork, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
40 A	3,420	SF	5" Hot Mix Asphalt (SX-75,PG 58-28) over 8" Class 6 Aggregate Base Course: including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
41 A	4,330	SF	2" Hot Mix Asphalt Overlay (SX-75,PG 58-28): including but not limited to: furnishing, tack coat, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
42 A	110	LF	Asphalt Edge Matching (T-Top): including but not limited to: milling, labor, equipment, hauling, and all materials necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
43 A	1	LS	Pavement Markings and Thermoplastics: including but not limited to: furnishing, surface preparation, templates, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

<b>Item No.</b>	<b>Estimated Quantity</b>	<b>Unit</b>	<b>Description and Unit Price in Words</b>	<b>Unit Price</b>	<b>Total Price</b>
44 A	3	EA	Paver Tree Grate: including furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
45 A	1	EA	Reinstall Salvaged Tree Grate: including concrete, furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
46 A	3	EA	Deciduous Tree, Root Barrier, Conditioned Soil and Mulch: including furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
47 A	3	EA	Fabricated Tree Guard: including furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
48 A	6.25	SF	New Sign Panel (Class 1): including but not limited to: furnishing, materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
49 A	2	EA	New Sign Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
50 A	2	EA	Reinstall Sign Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Sanitary Sewer - Grand Ave. to Colorado Ave.**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
51 A	1	LS	Force Account (for Minor Contract Revisions): including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.	\$ 35,000.00	\$ 35,000.00
(Lump Sum Price - Words)				(Numeric)	(Numeric)

**Total of All Items (Complete Project):** \_\_\_\_\_

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
1 B	1	LS	Mobilization, Demobilization and Incidentals: including but not limited to: all permits, coordination, labor, equipment, all other materials, services, safety, utility locates, excavations, soil preparations, site grading, vertical adjustments to existing utility structures or other items not individual itemized but required to effect construction, initiation, and completion of the project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
2 B	1	LS	Performance and Payment Bonds.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
3 B	1	LS	Construction Surveying and As-built Mapping: including but not limited to: all materials, labor and equipment necessary for establishing property line control, providing construction stakes, resetting damaged property corners or control markers, asbuilt mapping of all installed and encountered underground piping, for a complete project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
4 B	1	LS	Traffic Control: including but not limited: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
5 B	1	LS	Testing of Materials and Quality Assurance: including but not limited: coordination, material sampling, field and lab testing, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**  
**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
6 B	1	LS	Removal and Salvage of Materials (Signs, Posts, Bases, Lights, Furniture, Frames & Grates, etc.): including but not limited to: excavation, removal, hauling, delivery of salvaged materials, disposal of waste, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
7 B	1	LS	Removal and Salvage of Decorative Gravels & Road Base: including but not limited to: excavation, removal, hauling, delivery of salvaged materials, disposal of waste, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
8 B	1	LS	Removal of Pavement Markings (Sandblasting): including but not limited to: furnishing, hauling, all other materials, labor and equipment necessary for a completed project		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
9 B	735	SF	Removal of Concrete Sidewalk, Flatwork, Curb and Pavers: including but not limited to: removal, hauling, disposal, sawcuts, salvage of pavers and dome plates, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
10 B	6,000	SF	Removal of Asphalt (Disposal): including but not limited to: removal, stockpiling, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
11 B	1	LS	Erosion and Sediment Control: including but not limited to: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
12 B	530	LF	Trenching, Bedding & Backfill for Electric and Irrigation Conduits and Boxes: including but not limited to: coordination with City Electric Dept. (City to supply conduit, wire, pull boxes), excavation, bedding, conduit/wire/pull box installation, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
13 B	768	LF	Electric and Irrigation Conduits (2"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
14 B	84	LF	Electric and Irrigation Conduits (3"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
15 B	256	LF	Electric and Irrigation Conduits (4"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**  
**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
16 B	5	EA	Electric or Irrigation Box (Concrete): including but not limited to: coordination with City Electric Dept., excavation, bedding, box, backfill, compaction, all other materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
17 B	2	EA	Electrical Outlet Receptacle: including but not limited to: coordination with City Electric Dept., furnishing, all other materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
18 B	1	LS	Electrical System Wire and Electrician: including but not limited to: materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
19 B	1	EA	Light Pole Base: including but not limited to: coordination with City Electric Dept., excavation, bedding, backfill, compaction, concrete base (pole/lamp/wiring provided by others), all other materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
20 B	200	LF	Irrigation Main Extension(s): including but not limited to: excavation, bedding, backfill, compaction, conduit sleeving, pipe, valves, fittings, connections, boxes, testing, encasements, all other materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)



**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
21 B	1	LS	Irrigation Sprinkler System (for Lawn): including but not limited to: excavation, bedding, backfill, compaction, tubing, valves, fittings, heads, connections, wire, boxes, testing, encasements, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
22 B	3	EA	Core Ex. Storm Sewer Structure and Connect: including but not limited to: demolitions, furnishing, hauling, casting, formwork, adaptor boot, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
23 B	189	LF	Trench Drain & Concrete Support: including but not limited to: trench drain material, fittings, connections, concrete support, rebar, dowels, insulation, mortar set, excavation, bedding, furnishing, hauling, formwork, reinforcement, consolidation, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
24 B	2	EA	Nyloplast Storm Sewer Basin (Frame/Lid excluded): including but not limited to: furnishing, hauling, casting, formwork, reinforcement, consolidation, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
25 B	5	EA	Cleanout (Weep Hole & Storm Sewer): including but not limited to: furnishing, covers, hauling, casting, formwork, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
26 B	55	LF	Drainage Pipe (4"Ø PVC), Fittings & Adaptors (near Cooper Ave.): including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
27 B	170	LF	Drainage Pipe (6"Ø PVC), Fittings & Adaptors: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
28 B	30	LF	Drainage Pipe (8"Ø PVC), Fittings & Adaptors: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
29 B	124	LF	Drainage Pipe (15"Ø PVC), Fittings & Adaptors: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
30 B	14	EA	Valve Cover (12" Sq. Nyloplast Solid Cover): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
31 B	2	EA	Utility Access Cover (Wundercover WC60x60): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
32 B	3	EA	Utility Access Cover (Wundercover WC70x70): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
33 B	2	EA	Utility Access Cover (Wundercover WC90x90): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
34 B	1	EA	Utility Access Cover (Wundercover WC100x100): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
35 B	1	EA	Utility Access Cover Lift (Wunder-Lift and chains): including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
36 B	4	EA	Utility Access Cover Lift (WunderKey, 18" WK450): including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
37 B	300	LF	Weep Hole Underdrain: including but not limited to: pipe, fittings, liner, coring, connections, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
38 B	1	LS	Landscape Underdrain: including but not limited to: perforated pipe, solid pipe, fittings, adaptors, pipe boots, connections, cleanouts, covers, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <u>(Lump Sum Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
39 B	96	LF	12"Hx 1/2"Thick Cor-Ten Steel Edge Wall: including but not limited to: furnishing, hauling, welding, reinforcement, supports, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
40 B	968	SF	Geomembrane (30 Mil PVC): including but not limited to: furnishing, hauling, welding, fasteners, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
41 B	200	SF	CDOT Class-C Filter Media (6" Depth) around Landscape Underdrain: including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
42 B	220	SF	Geotextile (Filter Fabric): including but not limited to: furnishing, hauling, fasteners, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
43 B	48	CY	Amended Topsoil: including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
44 B	340	SF	3" Mulch: including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
45 B	1,000	SF	Sod: including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
46 B	70	LF	Curb and Gutter (IB, IIB, IM, IIM or Special): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
47 B	220	SF	4" Standard Gray Concrete (Sidewalks) over 6" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
48 B	7,130	SF	6" Standard Gray Concrete Pavement over 4" Class 6 Aggregate Base Course (Paver Underlayment-Sidewalks): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
49 B	1,980	SF	8" Standard Gray Concrete Pavement over 3" Class 6 Aggregate Base Course (Paver Underlayment-Roadways) : including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
50 B	382	SF	8" Colored Concrete Pavement over 8" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
51 B	175	SF	Detectable Warning Plate (at Crosswalk): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
52 B	155	SF	Concrete Paver Installation (Sand Set): including but not limited to: coordination with City Public Works Dept (City to supply concrete/clay pavers/spacers), aggregate base course, sand setting bed, compaction, furnishing, hauling, formwork, patterns, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
53 B	5,875	SF	Clay Pavers (Sand Set)(Sidewalks): including but not limited to: pavers, spacers, sand set bedding, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
54 B	1,395	SF	Clay Pavers (Mortar Set)(Roadway): including but not limited to: pavers, spacers, mortar, grout, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
55 B	1,740	SF	Stone Pavers Installation (Mortar Set)(Roadway, Centerline, Crosswalks & Sidewalks): including but not limited to: coordination with City Public Works Dept (City to supply stone pavers), mortar, grout, sealer, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)

**BID SCHEDULE**  
**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
56 B	2,100	SF	5" Hot Mix Asphalt (SX-75,PG 58-28) over 8" Class 6 Aggregate Base Course (nea Staircase): including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
57 B	220	SF	5" Hot Mix Asphalt (SX-75,PG 58-28) over 12" Class 6 Aggregate Base Course (near Cooper Ave.): including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
58 B	1	LS	Hot Mix Asphalt Infrared Joint: including but not limited to: furnishing, labor, equipment, and all materials necessary for a completed project.	(Numeric)	(Numeric)
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
59 B	1	LS	Pavement Markings and Thermoplastics: including but not limited to: furnishing, surface preparation, templates, all other materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
60 B	15.25	SF	New Sign Panel (Class 1): including but not limited to: furnishing, materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)
61 B	6	EA	New Sign Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.	(Numeric)	(Numeric)
			(Unit Price - Words)	(Numeric)	(Numeric)



**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
62 B	1	EA	Reinstall Sign: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
63 B	5	EA	Reinstall Sign(s) Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
64 B	71	EA	Bollard and Chain (Install Only): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
65 B	9	EA	Bollard Bases (Landscape Areas): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
66 B	1	LS	Reinstall Salvaged Furniture: including but not limited to: all materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
67 B	1	LS	Force Account (for Minor Contract Revisions): including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
				\$ 25,000.00	\$ 25,000.00
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
			<b>Total of All Items (Complete Project):</b>	_____	_____

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
----------	-----------------------	------	-------------------------------------	------------	-------------

**Alternates:**

Alternate pricing is requested to install Colored Concrete Pavement in the roadway in place of the Clay Pavers from Sta: 601 + 64.8 to 602 + 17.1. The Stone Pavers Installation (Mortar Set) shall remain with exception of the stone centerline stripes which shall be preplaced with epoxy pavement markings. This shall require the following changes to the Bid:

Alt-1 B	-1,980	SF	Delete Item#49B-8" Standard Gray Concrete Pavement over 3" Class 6 Aggregate Base Course (Paver Underlayment-Roadways)(Subtraction)(Unit Prices shall match previous)		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
Alt-2 B	-1,395	SF	Delete Item#54B-Clay Pavers (Mortar Set)(Roadway) (Subtraction)(Unit Prices shall match previous)		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
Alt-3 B	-36	SF	Reduce Quantity of Item#55B-Stone Pavers Installation (Mortar Set)(Roadway, Centerline, Crosswalks & Sidewalks)(Subtraction)(Unit Prices shall match previous)		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>
Alt-4 B	1,115	SF	8" Standard Gray Concrete Pavement over 3" Class 6 Aggregate Base Course (Paver Underlayment-Roadways) : including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <u>(Unit Price - Words)</u>	<hr/> <u>(Numeric)</u>	<hr/> <u>(Numeric)</u>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 1**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
Alt-5 B	865	SF	8" Colored Concrete Pavement over 8" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-6 B	630	SF	Clay Pavers (Mortar Set)(Crosswalks): including but not limited to: pavers, spacers, mortar, grout, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-7 B	1	LS	Additional Pavement Markings (Centerline): including but not limited to: furnishing, surface preparation, templates, all other materials, labor and equipment necessary for a completed project.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
<b>Total of All Items (Complete Project with Alternates):</b>					
_____					

**BID SCHEDULE****7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
1 C	1	LS	Mobilization, Demobilization and Incidentals: including but not limited to: all permits, coordination, labor, equipment, all other materials, services, safety, utility locates, excavations, soil preparations, site grading, vertical adjustments to existing utility structures or other items not individual itemized but required to effect construction, initiation, and completion of the project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
2 C	1	LS	Performance and Payment Bonds.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
3 C	1	LS	Construction Surveying and As-built Mapping: including but not limited to: all materials, labor and equipment necessary for establishing property line control, providing construction stakes, resetting damaged property corners or control markers, asbuilt mapping of all installed and encountered underground piping, for a complete project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
4 C	1	LS	Traffic Control: including but not limited: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
5 C	1	LS	Testing of Materials and Quality Assurance: including but not limited: coordination, material sampling, field and lab testing, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
6 C	1	LS	Removal and Salvage of Materials (Signs, Posts, Bases, Lights, Furniture, Frames & Grates, etc.): including but not limited to: excavation, removal, hauling, delivery of salvaged materials, disposal of waste, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Lump Sum Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
7 C	2	EA	Removal of Tree: including but not limited to: removal, hauling, disposal, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
8 C	4,235	SF	Removal of Concrete Sidewalk, Flatwork, Curb and Pavers: including but not limited to: removal, hauling, disposal, sawcuts, salvage of pavers and dome plates, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
9 C	305	LF	Removal of Vertical Concrete Wall: including but not limited to: removal, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
10 C	1	LS	Removal of Steel Handrail & Grout Holes: including but not limited to: removal, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Lump Sum Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
11 C	3,348	SF	Removal of Asphalt (Disposal): including but not limited to: removal, stockpiling, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
12 C	2,085	SF	Removal of Asphalt (Disposal)(From Phase 1): including but not limited to: removal, stockpiling, hauling, disposal, sawcuts, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
13 C	1	LS	Erosion and Sediment Control: including but not limited to: permitting, fees, reporting, all other materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
14 C	345	LF	Trenching, Bedding & Backfill for Electric and Irrigation Conduits and Boxes: including but not limited to: coordination with City Electric Dept. (City to supply conduit, wire, pull boxes), excavation, bedding, conduit/wire/pull box installation, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
15 C	155	LF	Electric and Irrigation Conduits (2"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
16 C	570	LF	Electric and Irrigation Conduits (3"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
17 C	105	LF	Electric and Irrigation Conduits (4"Ø): including but not limited to: coordination with City Electric Dept., excavation, bedding, conduit, fittings, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
18 C	1	EA	Electric or Irrigation Box (Concrete): including but not limited to: coordination with City Electric Dept., excavation, bedding, box, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
19 C	1	LS	Electrical System Wire and Electrician: including but not limited to: materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Lump Sum Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
20 C	4	EA	Light Pole Base: including but not limited to: coordination with City Electric Dept., excavation, bedding, backfill, compaction, concrete base (pole/lamp/wiring provided by others), all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
21 C	1	EA	Core Ex. Storm Sewer Pipe and Connect: including but not limited to: demolitions, furnishing, hauling, casting, formwork, adaptor, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
22 C	1	EA	New Inlet Cover and Grate (Inlet-C-708): including but not limited to: furnishing, hauling, casting, formwork, reinforcement, consolidation, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
23 C	1	EA	New Sanitary Sewer Service: including but not limited to: furnishing, hauling, excavation, insulation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
24 C	3	EA	Cleanout (Sanitary & Storm Sewer): including but not limited to: furnishing, Nyloplast cover, hauling, casting, formwork, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
25 C	2	EA	Utility Access Cover (Wundercover WC70x70): including but not limited to: furnishing, hauling, formwork, grout, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>



**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
26 C	470	LF	12"Hx 1/2"Thick Cor-Ten Steel Edge Wall: including but not limited to: furnishing, hauling, welding, reinforcement, supports, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
27 C	1	LS	Underdrain (Pervious Paver System): including but not limited to: perforated pipe, solid pipe, fittings, adaptors, pipe boots, connections, cleanouts, covers, excavation, bedding, backfill, compaction, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Lump Sum Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
28 C	66	LF	12"x12" Concrete Curb (Pervious Paver System): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
29 C	650	SF	Geomembrane (30 Mil PVC)(Pervious Paver System): including but not limited to: furnishing, hauling, welding, fasteners, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
30 C	370	SF	CDOT Class-C Filter Media (6" Depth)(Pervious Paver System): including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
31 C	982	SF	Geotextile (Filter Fabric)(Pervious Paver System & Drivable Grass Pavers): including but not limited to: furnishing, hauling, fasteners, testing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
32 C	370	SF	CDOT #67 Aggregate Base Course (6" Depth) (Pervious Paver System): including but not limited to: furnishing, labor, equipment, hauling, compaction, testing, and all materials necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
33 C	320	SF	Clay Pervious Pavers (Pervious Paver System): including but not limited to: pavers, spacers, aggregate bedding, furnishing, hauling, formwork, consolidation, patterns, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
34 C	48	SF	Stone Pavers (Black Granite,8"x24")(Pervious Paver System): including but not limited to: pavers, spacers, aggregate bedding, furnishing, hauling, formwork, consolidation, patterns, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>
35 C	24	CY	Amended Topsoil: including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
			<hr/> <p>(Unit Price - Words)</p>	<hr/> <p>(Numeric)</p>	<hr/> <p>(Numeric)</p>

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
36 C	111	LF	Curb and Gutter (IB, IIB, IM, IIM, Barrier, Ribbon or Special): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
37 C	20	SF	4" Standard Gray Concrete (Sidewalks) over 6" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
38 C	2,225	SF	4" Standard Gray Concrete Pavement over 4" Class 6 Aggregate Base Course (Paver Underlayment-Sidewalks): including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
39 C	4,135	SF	8" Standard Gray Concrete Pavement over 3" Class 6 Aggregate Base Course (Paver Underlayment-Roadways) : including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
40 C	930	SF	8" Colored Concrete Pavement over 8" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
41 C	12	SF	Detectable Warning Plate (at Crosswalk): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
42 C	242	SF	Geogrid (Driveway): including but not limited to: furnishing, hauling, fasteners, testing, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
43 C	242	SF	Drivable Grass Permeable Pavers (Sand Set)(Driveway): including but not limited to: pavers, spacers, sand set bedding, sealer, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
44 C	1,940	SF	Clay Pavers (Sand Set)(Sidewalks and Ramp): including but not limited to: pavers, spacers, sand set bedding, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
45 C	3,580	SF	Clay Pavers (Mortar Set)(Roadway & Parking): including but not limited to: pavers, spacers, mortar, grout, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
46 C	170	SF	Stone Pavers (Black Granite,4"x8")(Mortar Set)(Centerline Stripe & Ramp Strip): including but not limited to: pavers, spacers, mortar, grout, sealer, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
47 C	570	SF	Stone Pavers (Black Granite,8"x24")(Mortar Set)(Roadway, Parking, & North Sidewalk): including but not limited to: pavers, spacers, mortar, grout, sealer,furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
48 C	10	SF	Reinstall Salvaged Stone Pavers (Mortar Set) (Crosswalk): including but not limited to: mortar, grout, sealer, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)
49 C	100	SF	Sandstone Flagstones (Mortar Set)(South Sidewalk): including but not limited to: flagstones, spacers, mortar, grout, sealer, furnishing, hauling, formwork, consolidation, joints, patterns, all other materials, labor and equipment necessary for a completed project.		
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
50 C	6.00	SF	New Sign Panel (Class 1): including but not limited to: furnishing, materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
51 C	2	EA	New Sign Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
52 C	1	EA	New Slipbase: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
53 C	5	EA	Reinstall Sign(s) Post & Base: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
54 C	43	EA	Bollard and Chain (Install Only): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
55 C	30	EA	Bollard Bases (Landscape Areas & On Inlet): including but not limited to: all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)
56 C	152	LF	Pedestrian Railing: including but not limited to: furnishing, all materials, labor and equipment necessary for a completed project.		
			<hr/>	<hr/>	<hr/>
			(Unit Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
57 C	1	LS	Reinstall Salvaged Furniture: including but not limited to: all materials, labor and equipment necessary for a completed project.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
58 C	1	LS	Force Account (for Minor Contract Revisions): including but not limited to: furnishing, all other materials, labor and equipment necessary for a completed project.		
				\$ 25,000.00	\$ 25,000.00
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**Total of All Items (Complete Project):** \_\_\_\_\_

**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
----------	-----------------------	------	-------------------------------------	------------	-------------

**Alternates:**

Alternate pricing is requested to install Colored Concrete Pavement in the roadway and south parking area in place of the Clay Pavers. The Stone Pavers Installation (Mortar Set) shall remain with exception of the stone centerline stripes which shall be preplaced with epoxy pavement markings. This shall require the following changes to the Bid:

Alt-1 C	-4,135	SF	Delete Item#39C-8" Standard Gray Concrete Pavement over 3" Class 6 Aggregate Base Course (Paver Underlayment-Roadways)(Subtraction)(Unit Prices shall match previous)		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-2 C	-3,580	SF	Delete Item#45C-Clay Pavers (Mortar Set)(Roadway & Parking)(Subtraction)(Unit Prices shall match previous)		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-3 C	-140	SF	Reduce Quantity of Item#46C-Stone Pavers (Black Granite,4"x8")(Mortar Set)(Centerline Stripe & Ramp Strip)(Subtraction)(Unit Prices shall match previous)		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-4 C	-415	SF	Reduce Quantity of Item#47C-Stone Pavers (Black Granite,8"x24")(Mortar Set)(Roadway, Parking, & North Sidewalk)(Subtraction)(Unit Prices shall match previous)		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-5 C	4,135	SF	8" Colored Concrete Pavement over 8" Class 6 Aggregate Base Course: including but not limited to: soil preparation, aggregate base course, compaction, concrete, furnishing, hauling, casting, formwork, reinforcement, consolidation, joints, testing, all other materials, labor and equipment necessary for a completed project.		
			_____ (Unit Price - Words)	_____ (Numeric)	_____ (Numeric)



**BID SCHEDULE**

**7th Street Streetscape Beautification - Phase 2**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
Alt-6 C	1	LS	Pavement Markings: including but not limited to: furnishing, surface preparation, templates, all other materials, labor and equipment necessary for a completed project.		
			_____	_____	_____
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
			<b>Total of All Items (Complete Project with Alternates):</b>	_____	

**BID SCHEDULE**  
**Completion Date Alternatives**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
Incentive Fees are requested for completion of all work, including Project Closeout and Demobilization, of awarded projects before Thursday August 29, 2019. The following alternatives shall be considered:					
Alt-1 D	1	LS	Completion of all work for 7th Street Sanitary Sewer by Thursday, May 23, 2019; Completion of all subsurface work (ie. utilities and storm sewer) for 7th Street Streetscape Beautification-Phase 1 by Thursday, May 23, 2019; Completion of all surface work (ie. curb, concrete, stones, pavers, etc.) within the roadway and south of the roadway to the south right-of-way-line for 7th Street Streetscape Beautification-Phase 1 by Thursday, May 23, 2019 and; Completion of all remaining surface work north of the roadway for 7th Street Streetscape Beautification-Phase 1 by Tuesday, July 2, 2019.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
Alt-2 D	1	LS	Completion of all work for 7th Street Sanitary Sewer and 7th Street Streetscape Beautification-Phase 1 by Thursday, May 23, 2019.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)
Alt-3 D	1	LS	Completion of all work for 7th Street Sanitary Sewer by Tuesday, July 2, 2019; Completion of all subsurface work (ie. utilities and storm sewer) for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Tuesday, July 2, 2019; Completion of all surface work (ie. curb, concrete, stones, pavers, etc.) within the roadway and south of the roadway to the south right-of-way-line for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Tuesday, July 2, 2019 and; Completion of all remaining surface work north of the roadway for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Thursday August 29, 2019.		
			(Lump Sum Price - Words)	(Numeric)	(Numeric)

**BID SCHEDULE**  
**Completion Date Alternatives**

BUI Project No. 16024

10/15/2018, Rev. 11/29/18

Item No.	Estimated Quantity	Unit	Description and Unit Price in Words	Unit Price	Total Price
Alt-4 D	1	LS	Completion of all work for 7th Street Sanitary Sewer by Thursday, May 23, 2019; Completion of all subsurface work (ie. utilities and storm sewer) for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Thursday, May 23, 2019; Completion of all surface work (ie. curb, concrete, stones, pavers, etc.) within the roadway and south of the roadway to the south right-of-way-line for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Thursday, May 23, 2019 and; Completion of all remaining surface work north of the roadway for 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2</i> by Tuesday, July 2, 2019.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)
Alt-5 D	1	LS	Completion of all work for 7th Street Sanitary Sewer, 7th Street Streetscape Beautification-Phase 1 <i>and Phase 2 (All Projects)</i> by Thursday, May 23, 2019.		
			_____ (Lump Sum Price - Words)	_____ (Numeric)	_____ (Numeric)